



ADDENDUM #2

TITLE: Belle Glade Airport Lift Station Construction
FDOT Joint Participation Agreement #442007-
1-94-01

DATE: 3/11/2021

BID NO: 02-2021

BID OPENING DATE: 3/16/2021 @
3:00PM

NUMBER OF PAGES: 6

This Addendum to the drawings, specifications and contract documents is issued to provide additional information and clarification to the original bid specifications and ITB form and is hereby declared a part of the original drawings, specifications and contract documents. In case of conflict, this Addendum shall govern.

Bidders shall acknowledge receipt of this Addendum by inserting this Addendum in the attachment section of the Bid Form.

CONTENTS

1. DRAWING S C-1 AND C-2 REVISED PAGES. SEE ATTACHED.
2. SECTION 01150, REVISED PART 2.01 WORK COVERED BY THESE CONTRACT DOCUMENTS

THE BALANCE OF THIS PAGE IS INTENTIONALLY LEFT BLANK

CITY OF BELLE GLADE



Neil Appel, C.P.M.
Purchasing Manager


BIDDER

Signature

Printed, Title

COMPANY





TOWNSHIP - 37
RANGE - 43
SECTION - 29

CONSTRUCTION NOTES:

- [illegible]

CALL 2 WORKING DAYS
BEFORE YOU DIG

IT'S THE LAW!
DIAL 811

Know what's below.
Call before you dig.



WUD 20-579

SHEET NUMBER

C-2

PARTIAL SITE PLAN - EAST
GRAVITY LATERAL

LICENSED PROFESSIONAL
JASON R. LEE, P.E.
FLORIDA LICENSE NUMBER

**BELLE GLADE AIRPORT
LIFT STATION
PREPARED FOR
CITY OF BELLE GLADE**

KHA PROJECT	DATE	SCALE AS SHOWN	DESIGNED BY	DAC	DRAWN BY	RAR	CHECKED BY	GR
144086023	JAN. 2021							

Kimley»»Horn

[illegible][illegible][illegible]

ADDENDUM 2

REVISED SPECIFICATION 2.01F +2.01H

PROJECT TITLE: Belle Glade Airport Liftstation Construction FDOT Joint Participation Agreement #442007-1-94-01

TO: All Plan Holders of Record

This addendum forms a part of the Contract Documents and modifies the original Project Documents as noted below. **Acknowledge receipt of this Addendum in the space provided on the Bid Proposal form.**

GENERAL

RAI - 1

The route of the PVC gravity sewer line routes in close proximity to the rear of the existing office trailers and metal storage buildings. Are there underground utilities that are not shown on the drawings.

Response

Yes, the corridor between the perimeter fence and office trailers/metal buildings is known to have existing underground water services, phone lines, electrical conduit, and cable conduits that were not able to be located during the design and are not shown on the construction drawings. The contractor will be required to field locate and protect all existing underground utilities prior to commencing construction. Existing equipment including, but not limited to, air conditioning compressors, access stairs, and electrical panels are to be protected by the contractor. All costs related to utility locations and protection of existing equipment shall be included within the bid.

RAI - 2

The work is in close proximity to the perimeter fence. Is it permissible to remove the perimeter fence to provide additional access for construction?

Response

Yes, the perimeter fence can be temporarily removed but will be required to be completely restored to preconstruction condition prior to project completion. Temporary fencing will be required to be installed to maintain security through the construction duration. If the contractor chooses to temporarily remove sections of the fence for the project the removal and restoration costs, landscaping hedge replacement costs, and costs associated with temporary construction fencing are to be included in the bid.

IN THE SPECIFICATIONS

SECTION 01150, PART 2.01 WORK COVERED BY THESE CONTRACT DOCUMENTS

DELETE Paragraph 2.01F in its entirety and **REPLACE** it with revised Paragraph 2.01F as follows:

F. CIVIL/MECHANICAL IMPROVEMENTS (Item No. 6)

1. Method of Measurement: The quantity to be paid for under this Section shall be on a lump sum basis.
2. Basis of Payment: Payment shall be at the Contract Lump Sum Price and shall include, but not be limited to, furnishing all necessary equipment, labor, and materials required to remove surface materials and all protruding objects, excavation of any type of material including rock, trench safety, dewatering, utility locates, installation of new PVC gravity sewer and connections, installation of a new precast manhole structure, installation of a new water service, installation of a new valve vault with access hatch and coatings, wetwell with access hatch and coatings, concrete pad, fencing, installation of the lift station pumps as shown on the plans including rails, piping, fittings, valves, air release valve, instruments, pipe supports, control floats, connection to existing force main, testing, and start-up, and any other items required for a complete and functional system.

DELETE Paragraph 2.01H in its entirety and **REPLACE** it with revised Paragraph 2.01H as follows:

H. SITE RESTORATION (ITEM NO. 8)

1. Method of Measurement: The quantity to be paid for under this Section shall be on a lump sum basis.
2. Basis of Payment: Payment shall be at the Contract Lump Sum Price and shall include, but not limited to, furnishing, installing all the labor, equipment and materials required to restore the project area to an equal or better condition than what was existing prior to the start of the project or work within a particular area, including asphalt trench repair, sod, irrigation repairs, fencing, debris removal, painting, landscaping, or any other restoration and/or clean up required for a complete and functional system.

IN THE DRAWINGS

Sheet C-1

DELETE Sheet C-1 in its entirety and **REPLACE** it with revised Sheet C-1 included in this addendum. Revisions include the following:

- Northing and Easting locations are intended to be approximate. A "+/-" has been added to each coordinate.

DELETE Sheet C-2 in its entirety and **REPLACE** it with revised Sheet C-2 included in this addendum. Revisions include the following:

- Northing and Easting locations are intended to be approximate. A "+/-" has been added to each coordinate.
- Existing air conditioning compressor, access stairs, and electrical panel were more clearly noted on the site plan.

THIS SPACE WAS INTENTIONALLY LEFT BLANK
PROCEED TO NEXT PAGE